

Cost comparison for a new build house bathroom wall finishing
3m x 4m floor size, 34.6 m sq walls area

(**estimates from builderscrack.co.nz)

BEYOND TILES - FIBO SYSTEM

ITEMS	Low-end	Mid	High-end
Wall panels 24pc	\$2984.34	\$3735.65	\$4608.00
interior corners 4pc	\$137.4	\$137.4	\$137.4
Screws 2 box x 200pc	\$116.08	\$116.08	\$116.08
Fibo seal 4pc	\$100.93	\$100.93	\$100.93
Fibo wipes 1pc	\$22.42	\$22.42	\$22.42
Fibo clean 1pc	\$24.82	\$24.82	\$24.82
Installation 24 panels	\$1600.00	\$1600.00	\$1600.00
Total	\$4,986.05	\$5,737.3	\$6,008.60

WALLS PAINTED OR TILED

ITEMS	Wall paint/shower tiled	Walls fully tiled
Aqua gib	\$600.00	\$600.00
Gib fixing	\$450.00	\$450.00
Gib stopping	\$650.00	\$385.00
Painting	\$875.00	-
Finishing	\$300.00	-
Skirting	\$350.00	-
Waterproofing	\$500.00	\$500.00
Tiling	\$576.00	\$2975.00
Tiles	\$360.00	\$2450.00
Silicon joints	\$80.00	\$375.00
Project management	\$500.00	\$500.00
Total	\$5241.00	\$8235.00





COST COMPARISON

Cost comparison for a new build house bathroom wall finishing
3m x 4m floor size, 34.6 m sq walls area

(**estimates from builderscrack.co.nz)

DESCRIPTION	TILES/PAINT	BEYOND TILES – FIBO SYSTEM
Time of installation	73 hrs	12.5 hrs
Easy fitting	No	Yes
Budget friendly	No	Yes
Natural	No	Yes
Environment friendly	No	Yes
Neat and tidy	No	Yes
Washable	Yes	Yes
Budget friendly	No	Yes
Low maintenance	Yes	Yes
Hygienic	No	Yes
No dirty grouting	No	Yes
Warm to touch	No	Yes
Easy to cut	No	Yes
Light material	No	Yes
No mess	No	Yes

